

City of Decatur Building Department  
172 N 2<sup>nd</sup> St.  
Decatur, IN 46733

Curt A. Witte  
Superintendent

Office: (260) 724-3814  
Email: [cwitte@decaturin.org](mailto:cwitte@decaturin.org)

**ALL INSPECTIONS  
REQUIRE 24-HOUR NOTICE**

---

- |  |  |
|--|--|
| 1. Lot Lines, Layout & Utility Locates<br>Footing Inspection<br>(including post holes) | After excavation and foam is in place,<br>before pouring concrete  |
| 2. Foundation Inspection   | Crawl Space & Basement- after foundation walls are poured or<br>Block is laid  |
| 3. Underslab Plumbing<br>And Heating   | Prior to covering with fill  |
| 4. Slab Inspection   | Prior to pouring building slab or basement floor<br>(after wire and vapor barrier are installed)<br>(slab floor requires 5" between foam insulation and forms) |
| 5. Framing   | Before mechanical, plumbing and electrical system is installed and<br>Before enclosing walls within insulation or wall board                                   |
| 6. Rough Electrical  | Before enclosing walls & ceiling with insulation, wall board or panel  |
| 7. Electrical Service  | Prior to electric company hook-up.<br>Buried Services Entrances require final grading a lot  |
| 8. Rough Plumbing  | Before enclosing walls & ceiling with insulation or wall board   |
| 9. Rough Heating   | Before enclosing walls & ceiling with insulation or wall board   |
| 10. Draft & Fire Stopping  | Before enclosing walls with insulation-No foam unless approved by<br>Building Official   |
| 11. Sidewalks  | WHEN FORMED, PRIOR to pouring  |
| 12. Final Inspection   | PRIOR TO OCCUPANCY OF STRUCTURE  |

